

Site 1B

Research Triangle Park, North Carolina



TOTAL AREA

41 Acres*

BUILDING COVERAGE

6.15 Acres** (267,894 SQ FT)

PRICE

Please contact Carolyn Coia (busdev@rtp.org) at 919-433-1662

ROAD ACCESS

Access to Site 1B is from Davis Drive to the east. Widening of Davis Drive to 4 lanes, median divided is complete. Triangle Parkway runs along the west side of Site 1B.

WATER & SEWER

Durham County serves this site's sewer needs. The City of Durham serves this site's water needs. Sewer is along the north side of the site. Water lines are in Davis Drive.

ZONING

Science Research Park -
Durham Unified Development Ordinance

ELECTRICITY

Duke Energy serves this site. www.duke-energy.com

GAS

PSNC Energy serves this site. www.psnenergy.com

August 2018

Information is current through the above date

* All acreages are computer generated. Final acreages will be based on survey of property.

** Calculation of Building Coverage is based on the Durham Unified Development Ordinance which limits building footprint to 15% of total lot size.

*** Estimated price. Actual price will be determined by survey of property.




Site 1B

TOP RTP EMPLOYERS

- IBM
- Cisco
- Eli Lilly
- United Therapeutics
- NetApp
- Apple




Site 1B



MAP KEY


- Research Triangle Park
- Highway
- Road
- Stream
- Lake or Pond
- Railroad
- Recreation Area

Site 1B



LEGEND

STREAMS	ROADS
4 FT. CONTOURS	SURFACE COVER MAINTENANCE AREA
BUILDABLE AREA BOUNDARY	NATURAL AREA PRESERVE
BUILDABLE AREA	RAILROAD
BUILDING	SETBACK AREA
EASEMENT	LAKES



Zoning in the Research Triangle Park

Durham County

SCIENCE RESEARCH PARK

The SRP District is established to provide an area for business and scientific research and development, for training, and for production of prototype products, plans or designs in a low-density, open, campus-like setting. The purpose of such production is limited to research, development or evaluation of the merits of those products, plans or designs. The district is intended to accommodate research facilities, pilot plants, prototype production facilities and other manufacturing operations that require the continual or recurrent application of research knowledge and activity as an integral part of the manufacturing process. Offices and support services are allowed.

Durham's Unified Development Ordinance became effective January 1, 2006, replacing the previous Zoning and Subdivision Ordinances. For more information, please visit the Durham City/County Planning Department Web page.

LOT WIDTH

- At least 300 feet

YARD DIMENSIONS

- From public streets – 100 ft
- From adjoining lots – 100 ft
- No setbacks from adjacent railroads
- Yard area may not be devoted to parking, loading or storage.
- Where an area platted as permanent open space is located adjacent to a lot in the SRP district, the yard width may be reduced to 30 feet so long as building separation is at least 150 ft.

LOT COVERAGE

- A maximum of 15% if each lot shall be devoted to buildings. Parking structures are not included in this calculation.
- Parking may not be located in yard areas.

HEIGHT LIMITS

- The maximum building height shall be 120 feet.
- Additional height, up to 145 feet, may be allowed with Board of Adjustment approval.

